

Operations by Category

9/18/01 09:58:42

page 1 of 1

IN THIS REPORT: run[0003; Brandon Hospital Clean Utilities, [YES], This run is for the Clean Utilities only so that we can clear the Plumbers! Line#1078,Part#107108,Elv# 53] operation_category[0001; Assembly, 0002; Custom, 0005; Finish, 0003; Install, 0004; Panel Processing]

<u>Description</u>	<u>Time</u>	<u>Rate</u>	<u>Cost</u>	<u>Qty</u>	<u>Unit</u>
Brandon Hospital Clean Utilities					
Assembly					
Euro Type Hinge Plate Install	1.4	45.00	60.750	312.00	OCCURRENCES
Attach Sidemount Slide	2.9	45.00	130.500	115.00	OCCURRENCES
Install Wire Pull	3.2	45.00	143.250	222.00	OCCURRENCES
Drawer Front Fit & Adjust	3.7	45.00	165.403	64.00	OCCURRENCES
Door Hang & Adjust	5.8	45.00	262.702	157.00	OCCURRENCES
Assemble: Rail-Div-Partition-Fixed S	14.5	45.00	654.000	436.00	OCCURRENCES
Case Clamp	25.2	45.00	1132.500	122.00	OCCURRENCES
Finish					
Hand Sand Wood Edge	0.0	65.00	0.000	1465.51	FEET
Install					
Clean & Wrap	21.4	35.00	748.125	122.00	OCCURRENCES
Panel Processing					
Rip HP To Strips	.4	65.00	25.960	1395.68	FEET
Move Unit To Saw	.8	65.00	49.609	3447.91	SQUARE FEET
Face CNC Machining	2.1	65.00	138.667	54.00	OCCURRENCES
Euro Type Hinge Bore & Insert	2.7	65.00	175.500	314.00	OCCURRENCES
Edgebander Thin Rolled Material	3.0	65.00	191.819	429.33	FEET
Machine Wire Pull	6.3	65.00	409.067	222.00	OCCURRENCES
Face Boring Manual	6.9	65.00	448.933	256.00	OCCURRENCES
Edgebander HPL Strip Material	14.3	65.00	926.690	1395.68	FEET
Panel Saw Cut to Size	14.7	65.00	957.124	2163.20	SQUARE FEET
Edgebander Solid Wood Material	19.7	65.00	1281.657	1465.51	FEET
Edge Boring/Dowel Insert	37.8	65.00	2455.267	1474.00	OCCURRENCES
Subtotals	186.64		10357.52		
Grand Totals	186.64		10357.52		